Rocky Reach

- 11 generators
- Total generator nameplate capacity – 1,300 megawatts

Average yearly production (last 20 years) – 5.8 million megawatt hours

- 12 spillway gates
- Original construction started in 1956
- Commercial operation 1961 (seven generators)
- Four generators added in 1969-71
- Current power contract expiration:
 2011
- New FERC license Est. 2008





Rock Island

- 19 generators
- Generator nameplate capacity 624 megawatts

Average yearly production (last 20 years) – 3.0 million megawatt hours

- 31 spillway gates
- Original construction of First Powerhouse completed in 1933
- Capacity expanded in 1951-1953
- Second powerhouse constructed in 1979
- Current power contract expiration: 2012
- FERC license expiration: 2028



